

MINISTRY OF HEALTH & SOCIAL SERVICES
 SESFONTEIN CLINIC
 GENERATOR INSTALLATION

Section 1: General

ITEM	DESCRIPTION	UNIT	QTY	LABOUR RATE	MATERIAL RATE	TOTAL RATE	AMOUNT N\$
GENERAL							
	Tenderers shall allow for the following items whatever cost they may consider necessary for carrying out and observance of the item:						
1.1	Transport	Sum	1			0.00	0.00
1.2	Site Establishment	Sum	1			0.00	0.00
1.3	Setting Out	Sum	1			0.00	0.00
1.4	Progress Meetings	Sum	1			0.00	0.00
1.5	Attendance for measurement	Sum	1			0.00	0.00
1.6	Site Supervision	Sum	1			0.00	0.00
1.7	Insurance, Warranties	Sum	1			0.00	0.00
1.8	Telephone, stationery etc.	Sum	1			0.00	0.00
1.9	Tests and inspection prior to completion.	Sum	1			0.00	0.00
1.10	Production of "As-Built" drawings and all Operation and Maintenance Manuals, 3 Bound Copies of each	Sum	1			0.00	0.00
TOTAL CARRIED FORWARD							0.00

MINISTRY OF HEALTH & SOCIAL SERVICES
 SESFONTEIN CLINIC
 GENERATOR INSTALLATION

Section 2: Standby Generator(s)

ITEM	DESCRIPTION	UNIT	QTY	LABOUR RATE	MATERIAL RATE	TOTAL RATE	AMOUNT N\$
2	STANDBY GENERATOR(S)						
2.1	Supply, delivery and installation of automatic mains failure set as specified and as follows:						
	a) Genset, 75kVA prime, as detailed	No	1			0.00	0.00
	b) Generator Change over Board Controller, 100A/TP/CB	No	1			0.00	0.00
	c) Insulated low noise exhaust system	No	1			0.00	0.00
	d) Diesel in-built fuel tank and all piping, complete with first filling of fuel	Sum	1			0.00	0.00
	e) Set of spare water hoses	Sum	1			0.00	0.00
	f) Set of spare filters of all types required	Sum	1			0.00	0.00
	g) Set of spare V-belts	Sum	1			0.00	0.00
	h) All other equipment required for the set	Sum	1			0.00	0.00
	i) Dry type fire extinguisher on wall	No	2			0.00	0.00
2.2	Supply, deliver and installation of 1000V, Cu PVC SWAPVC cable						
	- 25mm ² x 4C	m				0.00	0.00
	- 16mm ² BCEW	m				0.00	0.00
	- Termination	No	4			0.00	0.00
2.3	Trenching in all material complete including backfill, bedding and compaction	m				0.00	0.00
TOTAL CARRIED FORWARD							0.00

MINISTRY OF HEALTH & SOCIAL SERVICES
 SESFONTEIN CLINIC
 GENERATOR INSTALLATION

Section 3: Testing Commissioning & Maintenance

ITEM	DESCRIPTION	UNIT	QTY	LABOUR RATE	MATERIAL RATE	TOTAL RATE	AMOUNT N\$
3	TESTING, COMMISSIONING & MAINTENANCE						
3.1	Testing & commissioning full load test	Sum	1			0.00	0.00
3.2	Cost required for the 12 month maintenance period including at least one site visit every 3 months for general electrical installation	Sum	1			0.00	0.00
3.3	Cost required for servicing of genset as recommended by manufacturer during 12 months maintenance period	Sum	1			0.00	0.00
TOTAL CARRIED FORWARD							0.00

MINISTRY OF HEALTH & SOCIAL SERVICES
SESFONTEIN CLINIC
GENERATOR INSTALLATION

SUMMARY OF SECTIONS

SECTION	DESCRIPTION						AMOUNT N\$
SECT 1	GENERAL						0.00
SECT 2	STANDBY GENERATORS						0.00
SECT 3	TESTING, COMMISSIONING &						0.00
	Sub-total						0.00
	CONTINGENCY 10%						0.00
	Sub-total						0.00
	ADD 15% VAT						0.00
TOTAL CARRIED FORWARD TO FORM OF TENDER							0.00